

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

9-22 BDF

### SAGINAW COUNTY REMONUMENTATION

RECORDED/FILED

### LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1999 SEP 29 A 8 08

For corners in

KOCHVILLE TOWNSHIP

SAGINAW Located in: Corner Code #  
(County)

- 1. Public Land Survey T13 N R 4 E M-8  
T      R
- 2. Property Controlling in Section S      T      R       
S      T      R
- 3. Miscellaneous Property in Sec. S      T      R       
S      T      R

MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

LIBER 2144 PAGE 756

*Liber 8 Page 21*

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Brian D Ferguson, in a field survey on JUNE 26, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7			8			9			10			11
5													
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													
12	31			32			33			34			35
13													

A. Description of original monument and accessories and/or subsequent restoration:

WOOD POST SET BY J. WAMPLER IN 1822, NO EVIDENCE OF ORIGINAL CORNER REMAINS  
LCRC BY JOHN MARTIN IN 1972, L 1, PG 240  
RECORDED SURVEYS IN L 1349, PG 448; L 1767, PG 1661

REGISTERED &  
RECORDED  
SEP 29 2000

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/8" ROD AT LOCATION PER LCRC. VERIFIED LOCATION PER DISTANCES TO ADJOINING SECTION CORNER FROM RECORDED SURVEYS

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET 5/8" REBAR W/ 3" BRASS CAP IN MONUMENT BOX
- S35E 41.74' REBAR 1' EAST OF ROAD
- S25W 43.35' REBAR 1' WEST OF ROAD IN GRASS
- S55E 28.29' FCE PWR POLE
- N40E 36.65' REBAR 1' NORTH OF DIRT PATH

Signed by Brian D Ferguson  
Surveyor's Michigan License No. 26454

Date

