

MAR 17 1999

BAY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Form with fields for County (BAY), Located In, Corner Code #, and numbered sections 1-5 for survey details.

REGISTER OF DEEDS BAY COUNTY, MICHIGAN 1999 JAN -5 A 9: 10 RECORDED Register of Deeds Stamp & File Number

I, DALE L. WINIECKE, in a field survey on SEPTEMBER 10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-7 SET POST, J. WAMPLER D.S., 1821 36" BLACK OAK S 16° W 25 LINKS 7" HICKORY N 42° E 5 LINKS

L.C.R.C., L.2, P.235, J. MARTIN PS# 4699, (1974) FOUND MON. BOX WITH 1/2" IRON ROD L.C.R.C., L.2, P.359, M. MACDONALD PS# 22438, (1976) A-7 T13N R6E, NO DESCRIPTION CERTIFICATE OF SURVEY, L.1579, P.2151, E. GOSS PS# 16040, (1979), FOUND MON. BOX 1997 SAGINAW CO. REMONUMENTATION LCRC, L. 2027, P. 468

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 FOUND 5/8" REBAR WITH SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX.

IN 1997 SAGINAW CO. REMONUMENTATION FOUND 5/8" REROD IN MONUMENT BOX. LOCATION VERIFIED FROM WITNESSES (L.C.R.C., L.2, P.235; L.C.R.C., L.2, P.359 AND SURVEY, L.1579, P.2151). ACCEPTED MONUMENT AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 FOUND 5/8" X 18" LONG REROD WITH SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX.

N 60° E 43.18' TO NAIL AND TAG IN NORTHWEST FACE OF P.P. N 70° E 21.45' TO 3/8" REROD WITH CAP #22438 S 45° E 39.26' TO 3/8" REROD WITH CAP #22438 S 45° W 42.33' TO NAIL AND TAG IN NORTHWEST FACE OF P.P. S 60° W 41.45' TO CENTERLINE OF PIPELINE MARKER N 50° W 56.87' TO NAIL AND TAG IN NORTHWEST FACE OF 24" MAPLE

APPROVED LAND CORNER P.A. 345 OF 1990 - Bay County Date 12 Nov 98 M.T.M. Michael MacDonald P.S. County Representative



Signed by Dale Winiecke Surveyor's Michigan License No. 41915

Date 12/30/98