

JAN 17 1999

BAY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>BAY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>6E</u>	<u>A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN
 1999 JAN -5 A 9:10
 RECORDED
 Register of Deeds Stamp & File Number

I, DALE L. WINIECKE, in a field survey on SEPTEMBER 10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-9

SET POST, J. WAMPLER D.S., 1821
 16" ASH, N 88-1/2° E 10 LINKS
 18" ASH, N 19° W 22 LINKS

1960 EDMANDS ENGINEERING, CONSUMERS POWER RIGHT OF WAY SURVEY, SET 3/8" REROD CERTIFICATE OF SURVEY, L.1135, P.271, D. BURGINS PS# 29240, (1989), FOUND 3/8" IRON CERTIFICATE OF SURVEY, L.1135, P.285, D. BURGINS PS# 29240, (1990), FOUND 3/8" IRON L.C.R.C. L.2, P.658, D. BURGINS PS# 29240, (1991), FOUND 3/8" IRON

1997 SAGINAW CO. REMONUMENTATION LCRC, L. 2027, P. 470

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9

FOUND 5/8" REBAR WITH SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX.

IN 1997 SAGINAW COUNTY REMONUMENTATION FOUND A 3/8" REROD PER RECORDED WITNESSES (BAY COUNTY L.1135, P.271; BAY COUNTY L.1135, P.285; L.2, P.658). ALSO FOUND 3/8" REROD 51.94' SOUTH USED IN SURVEY L.1579, P.2151 AND IN SAGINAW COUNTY ROAD COMMISSION WITNESSES.
 THE 3/8" REROD TO THE NORTH WAS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9

FOUND 5/8"x18" REROD WITH SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX.

N 75° E 41.87' TO NAIL AND TAG IN WEST FACE OF U.P.
 S 60° E 62.62' TO NAIL AND TAG IN SOUTHWEST FACE OF U.P.
 SOUTH 51.94' TO 3/8" REROD
 S 25° W 25.64' TO NAIL AND TAG IN TOP OF HEADWALL
 S 40° W 78.22' TO TOP CENTERLINE OF PIPELINE MARKER
 S 80° W 41.29' TO TOP CENTERLINE OF PIPELINE MARKER
 S 70° W 29.04' TO NAIL AND TAG IN NORTH FACE OF U.P.

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 12 Nov 98
MJM
 Michael MacDonald P.S.
 County Representative



Signed by Dale Winiecke
 Surveyor's Michigan License No. 41915

Date 12/30/98