

MAR 17 1999

BAY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Form with fields for County (BAY), Located In (T 13N R 6E), and Corner Code # (A-11). Includes checkboxes for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

RECORDED 1999 JAN -5 A 9:10 Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

I, DALE L. WINIECKE, in a field survey on SEPTEMBER 10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-11

SET POST, J. WAMPLER D.S., 1821 16" ASPEN, N 1° E, 17.79 CHAINS

1968 EDMANDS ENGINEERING, CONSUMERS POWER RIGHT OF WAY SURVEY, SET 3/8" REROD CERTIFICATE OF SURVEY, L.781, P.544, L. MCGINNIS PS# 18999, (1976), FOUND 3/8" REROD CERTIFICATE OF SURVEY, L.1585, P.719, M. MACDONALD PS# 22438, (1980), FOUND 3/8" REROD

1997 SAGINAW CO. REMONUMENTATION LCRC L. 2027, P. 472.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11

FOUND 5/8" REBAR WITH SAGINAW COUNTY REMONUMENTATION CAP

IN 1997 SAGINAW COUNTY REMONUMENTATION RESET CORNER USING WITNESSES FROM L.1585, P.544. CORNER USED IN L.1585, P.544 WAS RESET USING INFORMATION FROM 1968 EDMANDS ENGINEERING CONSUMERS POWER RIGHT OF WAY SURVEY. LOCATION WAS ACCEPTED AS THE BEST EVIDENCE OF THE ORIGINAL POSITION OF THE CORNER.

ALSO FOUND IN THE AREA WAS A 3/8" REROD 106.46' EAST OF THE RESET M-11. THIS CORNER WAS USED IN A BAY COUNTY SURVEY L.1135, P.271 AND BAY COUNTY SURVEY, L.1135, P.285. ANOTHER 3/8" REROD WAS FOUND SOUTH 142', THE ONLY RECORDED INFORMATION FOR THIS POINT IS THAT IT IS A WITNESS FOR THE RESET M-11 ABOVE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11

FOUND 5/8" X 18" LONG REROD WITH SAGINAW COUNTY REMONUMENTATION CAP IN FARM FIELD 20" BELOW THE SURFACE.

EAST 106.46' TO 3/8" REROD IN JONES ROAD S 35°E 189.00' TO WEST FACE OF WEST SIGN LEG S 55° E 173.75' TO NAIL AND TAG IN NORTH FACE OF U.P. SOUTH 142.00' TO 3/8" REROD IN CENTERLINE OF KRABBE ROAD AND JONES ROAD SOUTH S 20° W 133.51' TO TOP CENTERLINE OF PIPELINE MARKER

APPROVED LAND CORNER P.A. 345 OF 1990 - Bay County Date 12 Nov 98 M.J.M. Michael MacDonald P.S. County Representative

Signed by Dale Winnick Surveyor's Michigan License No. 41915

Date 12/30/98



Grid table with columns A-M and rows 1-13. Cell (10, 1) contains a small symbol.