

MAR 17 1999

BAY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Form with fields for County (BAY), Located In (T 13N R 6E), and Corner Code # (A-12). Includes sections for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

REGISTER OF DEEDS BAY COUNTY, MICHIGAN. 1999 JAN -5 A 9: 10. RECORDED. Register of Deeds Stamp & File Number.

4. Lot No. , Recorded Plat
5. Private Claims

I, DALE L. WINIECKE, in a field survey on SEPTEMBER 10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. Contains numbers 6 through 36.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-12
SET POST, J. WAMPLER D.S., 1821
NO TREES

1997 SAGINAW CO. REMONUMENTATION LCRC L. 2027, P, 473.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-12
FOUND 5/8" REBAR WITH SAGINAW COUNTY REMONUMENTATION CAP
IN 1997SAGINAW CO. REMONUMENTATION FOUND 3/4" PIPE 5" BELOW GRAVEL SURFACE. NO OTHER MONUMENTS FOUND IN THE AREA. DISTANCE FROM SPICER NOTES (NO DATE) FITS DISTANCE FROM M13 AND DISTANCE FROM M12 TO FOUND 3/8" REROD IN CENTERLINE OF JONES ROAD AND KRABBE ROAD. MONUMENT ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12
FOUND 5/8" X 18" REROD WITH SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX.
N 30° E 66.45' TO NAIL AND TAG IN SOUTHEAST FACE OF 36" POPLAR
N 55° E 36.50' TO SOUTH FACE OF SIGN POST
N 60° W 11.85' TO SOUTH FACE SOUTH SIGN LEG
N 75° W 44.97' TO EAST FACE OF PIPELINE MARKER
S 70° W 46.51' TO EAST FACE OF PIPELINE MARKER

APPROVED LAND CORNER
P.A. 345 OF 1990 - Bay County
Date 12 Nov 98
MJM
Michael MacDonald P.S.
County Representative



Signed by Dale Winiecke Date 12/30/98
Surveyor's Michigan License No. 41915