

MAR 17 1999

**BAY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in SECTION

<u>BAY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>6E</u>	<u>A-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Richard Thomas Oldham
 REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN
 1999 JAN -5 A 9: 10
 RECORDED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, DALE L. WINIECKE, in a field survey on SEPTEMBER 10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-13
 SET POST, J. WAMPLER D.S., 1821
 11" ASH, N 60° W 7 1/2 LINK
 12" ELM, N 3° E 7 LINKS

1997 SAGINAW CO. REMONUMENTATION LCRC L. 2027, P. 474

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13
 FOUND 5/8" REBAR WITH SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX
 IN 1997 SAGINAW CO. REMONUMENTATION FOUND 1/2" REROD 5" BELOW ASPHALT SURFACE. NO OTHER MONUMENTS FOUND IN THE AREA. SPICER NOTES (NO DATE) FIT THE DISTANCE BETWEEN M13 AND M12.
 MONUMENT ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13
 FOUND 5/8" X 18" REROD WITH SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX.
 N 40° E 31.04' TO CENTERLINE OF SIGN POST
 N 45° 3E 27.17' TO 3/8" REROD WITH CAP #22438
 S 45° E 20.08 TO 3/8" REROD WITH CAP #22438
 S 30° E 25.10' TO CENTERLINE OF ROAD SIGN POST
 S 47° W 23.25' TO 3/8" REROD WITH CAP #22438
 S 50° W 63.55' TO CENTERLINE OF PIPELINE MARKER
 N 60° W 50.45' TO CENTERLINE OF PIPELINE MARKER
 N 45° W 30.12' TO 3/8" REROD WITH CAP #22438

APPROVED LAND CORNER
 P.A. 945 OF 1999 - Bay County
 Date 12/30/98
MJM
 Michael MacDonald P.S.
 County Representative



Signed by Dale Winiecke
 Surveyor's Michigan License No. 41915

Date 12/30/98