

SURVEY A
REMONUMENTATION

MAR 31 1994

COMMISSIONER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
BAY COUNTY REMONUMENTATION PROJECT - 1993

LIBER 003 PAGE 58

REGISTER OF DEEDS
BAY COUNTY, MICHIGAN

JAN 27 1 45 PM '94

RECORDED

Register of Deeds Stamp & File Number

For corners in

BAY (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>13N</u> - R <u>6E</u>	<u>K-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Duane F. Ledy, in a field survey on DECEMBER 27, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
Post set at 40.00 chains North of K-9 (1834)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 3/4" pipe on side; C.P.Co. in survey dated in 1972 stated computed corner to be 1/2 way and on line between K-7 and K-9; no other surveys of L.C.R.C. of record were found; corner position accepted at mid-point in line between K-7 and K-9 by Bay County Peer Review Group, ratified on Nov. 24, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8 rod and Bay County brass cap in monument box.
N 85° W -32.44' Nail & Tag in Power Pole.
EAST -36.52' 1/2 X 18" rod W/21575 Cap
NORTH -2630.32' Corner K-7
SOUTH -2630.32' Corner K-9
-Corner at East edge of Chip & Seal



Signed by Duane F. Ledy Date January 13, 1994
Surveyor's Michigan License No. 21575