

SURVEY & REMONUMENTATION

MAR 31 1994

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
BAY COUNTY REMONUMENTATION PROJECT - 1993

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>13</u> N. S.; R. <u>6</u> E. W.	<u>L-7</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

LIBER 003 PAGE 64

JAN 27 1 46 PM '94

REGISTERED PROFESSIONAL SURVEYOR
BAY COUNTY, MICHIGAN

RECORDED

REGISTER OF DEEDS STAMP AND FILING NUMBER


I, Duane F. Ledy, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on DECEMBER 27, 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19 ____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Set post at 40.29 chains on line corrected between K-7 and M-7 (1834).

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Found PK nail on edge of pavement; M.S.H.D. found 1" iron and witnessed in 1966; C.P.Co. found PK nail and M.S.H.D. washer at mid-point between K-7 and M-7, 4.63' north of straight line between K-7 and M-7; surveys in 1979 and 1983 recorded in L866, P488 and L951, P402, perpetuate corner. Corner position accepted by Bay County Peer Review Group and ratified on November 24, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Replaced PK nail with 5/8" rod and Bay County brass cap in monument box.

- South - 9.2' Centerline of Highway M-138
- N 45° W - 36.16' Nail & Tag in Wood Post at Bell Riser
- S 45° W - 105.75' Nail & Tag in Power Pole
- S 10° W - 65.87' Nail & Tag in Power Pole
- N 45° E - 139.40' SE corner of House #1761



SIGNED BY Duane F. Ledy DATE January 13, 1994
 SURVEYOR'S MICHIGAN REGISTRATION NO. 21575 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
 CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____