

SURVEY & REMONUMENTATION
 MAR 31 1994
 COMMISSION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 BAY COUNTY REMONUMENTATION PROJECT - 1993

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>13</u> N. S. R. <u>6</u> E. W.	<u>L-9</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		


LIBER. **003** PAGE **65**
 REGISTERED OF DEEDS
 BAY COUNTY, MICHIGAN
 JAN 27 1 41 PM '94
 RECORDED
 REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Duane F. Ledy, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on DECEMBER 27, 1992, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 Post set at 40.25 chains on line corrected between K-9 and M-9 (1834).

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Found 1/2" rod; C.P.Co. found 1/2" rod on survey dated August 1972; Survey recorded in L 716, P 608 dated 1973 and L.C.R.C.'s in L 001, P 195-198 dated in 1972 and 1973 perpetuate the 1/2" rod; Corner accepted by Bay County Peer Review Group and ratified on October 18, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Replaced 1/2" rod with 5/8" rod and Bay County brass cap in monument box.
 N 45° W - 38.20' Nail & Tag in Power Pole
 S 45° W - 68.29' Nail & Tag in Power Pole
 N 45° E - 21.11' SW corner at base of concrete headwall
 S 45° E - 21.00' NW corner at base of concrete headwall



SIGNED BY Duane F. Ledy DATE January 13, 1994
 SURVEYOR'S MICHIGAN REGISTRATION NO. 21575 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
 CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____