

REMON. COR. A-6, WILLIAMS TWP.
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

SECTION

For corners in
 Bay _____
 (County)

Located in: Comer Code #
 T 14N R 3E A-6
 T ___ R ___
 T ___ R ___
 T ___ R ___
 S ___ T ___ R ___
 S ___ T ___ R ___
 S ___ T ___ R ___
 S ___ T ___ R ___

1999 DEC 28 P 1:01

Barbara Torres De Jesus
 REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

I, **JERRY L. JONES**, in a field survey on June 18, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-6 1/4 corner common to Section 18 on West Townline
 Survey by Hunter-Whittier 1974, 1977, 1978, 1979, found 1/2" rod
 Survey by Ayres Associates, 1983, found bolt spike
 Survey by Wade-Trim, 1992, set pk
 LCRC by D. Whittier, 1974, found boat spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6 1/4 Corner common to Section 18 on West Townline
 Found 1 1/4" pipe 2' deep at position indicated in surveys by Hunter-Whittier, Ayres Associates, Wade-Trim and LCRC by D. Whittier.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 1/4 Corner common to Section 18 on West Townline
 Found 1 1/4" pipe, replace pipe with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838 in monument box and is accepted as the best available evidence of the position of the accepted corner.
 N 45 Deg E, 59.77', centerline top fire hydrant
 S 35 Deg W, 116.97', pk nail in power pole
 N 85 Deg W, 54.69', pk nail in power pole
 N 85 Deg W, 54.28', railroad spike in power pole (Rec.)
 N 25 Deg E, 126.67', nail in telephone pole stub (Rec.)
 N 10 Deg ± E, 4.57', 3/8" rod in monument box M-6 Midland Co.



Signed by *Jerry L. Jones*
 Surveyor's Michigan License No. 19838

Date 12/22/99
 Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
 Revised May 14, 1971
 Revised Jan., 1983

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 9.30.99
MH
 Michael MacDonald P.S.
 County Representative