

**REMON. COR. B-5, WILLIAMS TWP.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

SECTION

For corners in
Bay _____
(County)

- | | | |
|---------------------------------------|-------------------------|---------------|
| 1. Public Land Survey | Located in: | Corner Code # |
| | T 14N R 3E | B-5 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

1999 DEC 28 P 1:01

Barbara Teresa DePasse
REGISTER OF DEEDS
BAY COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, **JERRY L. JONES**, in a field survey on _____, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-5 1/4 Corner common to Sections 7 and 18

Survey by Glo, 1830's, set post
Survey by Edmands Engineering, 1972, 1988, 1991, 1993, found 1/2" pipe
Survey by Hammond Engineering, 1975

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5 1/4 Corner common to Sections 7 and 18


Found 1/2" pipe at position indicated in surveys by Edmands Engineering and Hammond Engineering

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5 1/4 Corner common to Sections 7 and 18

Found 1/2" pipe, replaced pipe with 5/8" rod with brass cap stamped Bay County Remonumentation PS 19838 in monument box and accepted as the best available evidence of the position of the accepted corner.

N 5 Deg E, 38.12', Northeast corner box culvert (38.07' Rec.)
N 45 Deg W, 52.42', Northwest corner box culvert (52.34' Rec.)
S 70 Deg E, 91.15', centerline top fire hydrant
N 50 Deg E, 87.48', nail in power pole



Signed by *Jerry L. Jones*
Surveyor's Michigan License No. 19838

Date 12/22/99
Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
Revised May 14, 1971
Revised Jan., 1983

004 295

APPROVED LAND CORNER
P.A. 345 OF 1990 - Bay County
Date 7.09.99
MM
Michael MacDonald P.S.
County Representative