

**REMON CORNER D-5, WILLIAMS TWP.
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1999 DEC 28 P 1:01

Barbara Torres
REGISTER OF DEEDS
BAY COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

For corners in
Bay
(County)

SECTION

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>14N</u> R <u>3E</u> | <u>D-5</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling
in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous
Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

I, Jerry L. Jones, in a field survey on ^{July 22} ~~March~~, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- D-5 ¼ Corner common to Sections 8 and 17
- Survey by Glo, 1831, set post
Survey by G. Turner, 1908, found old corner
Survey by J. Schafer 1978, found 3/8" rod
Survey by D. Ledy, 1986, found 1/2" pipe
Wade-Trim, 1991, found 1/2" pipe
LCRC by K. Pomaville, 1999, found 1/2" pipe over bent 3/8" rod



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-5 ¼ Corner common to Sections 8 and 17
- Found 1/2" re-rod per surveys by J. Schafer, D. Ledy, Wade-Trim, and LCRC by K. Pomaville

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-5 ¼ Corner common to Sections 8 and 17
- Replaced 1/2" rod with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838 in mon box; and is accepted as the best available evidence of the position of the accepted corner
- S 5 Deg E, 40.91', nail and Bay Co disc in 12" Elm (rec)
S 60 Deg E, 65.31', nail and Bay Co disc in 6" Elm
North 33.03', centerline 2" pipe
S 25 Deg E, 149.10', NE corner (block) house

Signed by Jerry L. Jones
Surveyor's Michigan License No. 19838

Date 12/10/99
Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
Revised May 14, 1971
Revised Jan., 1983

004 301

APPROVED LAND CORNER
P.A. 345 OF 1990 - Bay County
Date 9-23-99
MH
Michael MacDonald P.S.
County Representative