

REV 1999

REMON. COR. D-9, WILLIAMS TWP. LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Bay (County)

- 1. Public Land Survey Located in: T 14N R 3E Corner Code # D-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

REGISTER OF DEEDS BAY COUNTY, MICHIGAN

1998 DEC -7 A 8:39

RECORDED

Register of Deeds Stamp & File Number

I, JERRY JONES, in a field survey on August 12, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-9 1/4 Corner common to Sections 20 and 29
Survey by Glo, Harvey Parke, 1831, set post
Survey by MDOT 1957, found 6" stone
Section corner card by Blass Surveys, stone, no date
Survey by Hunter-Whittier 1968, stone (set concrete monument)
Survey by Ayres Associates 1988, found monument

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-9 1/4 Corner common to Sections 20 and 29
Found concrete monument per surveys by MDOT, Hunter-Whittier and Ayres Associates.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-9 1/4 Corner common to Sections 20 and 29
Found concrete monument per surveys by MDOT, Hunter-Whittier and Ayres Associates. Set brass cap on rerod in monument; and is accepted as the best available evidence of the position of the accepted corner.
N 70 Deg W, 2.66', nail & BC disc in 6" Ash
N 20 Deg W, 18.72', nail & BC disc in 8" Ash
S 30 Deg W, 17.43', nail & BC disc in 6" Ash
S 40 Deg E, 52.46', nail & BC disc in 12" Cottonwood
West 75.4', center line Northbound M-47

APPROVED LAND CORNER P.A. 345 OF 1990 - Bay County Date 24 Sept 98 M.J.H. Michael MacDonald P.S. County Representative

Signed by Jerry L. Jones Date 12/01/98

Surveyor's Michigan License No. 19838

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971

Revised May 14, 1971

Revised Jan., 1983