

MAR 17 1999

REMON. COR. D-13, WILLIAMS TWP.  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in  
Bay  
 (County)

1. Public Land Survey	Located In:	Corner Code #
	T <u>14N</u> R <u>3E</u>	<u>D-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Barbara Foster  
 REGISTER OF DEEDS  
 BAY COUNTY, MICHIGAN

1998 DEC -7 A 8:37

RECORDED

Register of Deeds Stamp & File Number

I, JERRY JONES, in a field survey on June 26, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

D-13 South 1/4 corner Section 32

Survey by Gio, Joseph Wampler, 1822, set post  
 Survey by MDOT 1959, set 1" rod in mon box  
 Survey by Hunter and Whittier 1968, found mon box  
 Survey by Edmands Engineering 1974, 1975, found mon box  
 LCRC by L. McGinnis 1977, mon box



**WITNESS NOTE:** Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

D-13 South 1/4 corner Section 32

Found 1" rod 30" long in mon box (dug 3' found nothing) per surveys by MDOT, Hunter and Whittier, Edmands Engineering and LCRC by L. McGinnis

Corner \_\_\_\_\_ was approved for remonumentation at a Peer Review Committee Meeting on \_\_\_\_\_

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

D-13 South 1/4 corner Section 32

Found 1" rod in mon box per surveys by MDOT, Hunter and Whittier, Edmands Engineering, and LCRC by L. McGinnis; replaced rod with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838 and is accepted as the best available evidence of the position of the accepted corner.

Southeast 43.48' to northwest corner of west concrete post of south guardrail (Rec. as 43.5)  
 Northeast 43.52' to southwest corner of west concrete post of north guardrail (Rec. as 43.5)  
 S 45 Deg E, 19.34', pk nail in top guardrail post  
 S 40 Deg W, 19.06', pk nail in top guardrail post  
 N 50 Deg W, 25.19', pk nail in top guardrail post  
 N 50 Deg E, 22.50', pk nail in top guardrail post  
 East 40.7', West edge of overpass bridge  
 Saginaw Co. corner not found

APPROVED LAND CORNER  
 P.A. 345 OF 1990 - Bay County  
 Date 24 Sept 98  
MJM  
 Michael MacDonald P.S.  
 County Representative

Signed by Jerry L. Jones Date 12/01/98

Surveyor's Michigan License No. 19838