

RECORDED

REMON CORNER E-4, WILLIAMS TWP.  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1999 DEC 28 P 1:01

*Barbara Torres DeArmas*  
REGISTER OF DEEDS  
BAY COUNTY, MICHIGAN

For corners in  
Bay \_\_\_\_\_  
(County)

SECTION

Located in: Corner Code #

- 1. Public Land Survey  
T 14N R 3E      E-4  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling in Section  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec.  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, Jerry L. Jones, in a field survey on July 26, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

- E-4    ¼ Corner common to Sections 8 and 9  
Survey by Glo, 1831, set post  
Survey by G. Turner, 1908, found old corner  
Survey by J. Schafer 1979, found 1 ½" pipe



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-4    ¼ Corner common to Sections 8 and 9  
Found 3/8" rod and large nail 2 ft. below surface at position per surveys by G. Turner and J. Schafer

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-4    ¼ Corner common to Sections 8 and 9  
Replaced rod with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838 in mon box; and is accepted as the best available evidence of the position of the accepted corner  
West 33.80', nail and disc in fence post  
S 80 Deg E, 26.32', mag nail in bag concrete hdwl  
S 35 Deg E, 40.72', mag nail in bag concrete hdwl  
West 1.0', centerline bit road  
N 1 Deg W, 931.43', SW corner of bridge

Signed by Jerry L. Jones  
Surveyor's Michigan License No. 19838

Date 12/10/99

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971  
Revised May 14, 1971  
Revised Jan., 1983

004 304

APPROVED LAND CORNER  
P.A. 345 OF 1990 - Bay County  
Date 12-30-99  
MH  
Michael MacDonald P.S.  
County Representative