

REMON CORNER E-6, WILLIAMS TWP.
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in
 Bay _____
 (County)

SECTION

1. Public Land Survey

Located in: Corner Code #

T 14N R 3E _____ E-6

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
 in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
 Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1999 DEC 28 P 1:02
Barbara Tonka Old Person
 REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN
 Register of Deeds Stamp & File Number

I, Jerry L. Jones, in a field survey on June 18, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-6 1/4 Corner common to Sections 16 and 17

Survey by Glo, 1831, set post
 Survey by Edmands Engineering, 1971, found
 Survey by J. Schafer 1978, 1979, found 1/2" pipe, 30" deep raised with 3/8" rod in 1978

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6 1/4 Corner common to Sections 16 and 17

Found 3/8" rod over 1/2" pipe per surveys by Edmands Engineering and J. Schafer

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6 1/4 Corner common to Sections 16 and 17

Replaced rod with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838 in mon box; and is accepted as the best available evidence of the position of the accepted corner

N 70 Deg W, 40.38', pk nail in power pole
 West 44.90', nail in twin 12" Ash
 S 20 Deg E, 104.70', nail and plastic disc in 24" Maple
 S 20 Deg W, 67.88', N'y bolt on box culvert

Signed by Jerry L. Jones
 Surveyor's Michigan License No. 19838

Date 12/10/99
 Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
 Revised May 14, 1971
 Revised Jan., 1983



004 306

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 12/30/99
MH
 Michael MacDonald P.S.
 County Representative