

**REMON CORNER E-7, WILLIAMS TWP.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

For corners in
Bay _____
(County)

SECTION

Located in: Corner Code #

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>14N</u> R <u>3E</u> | <u>E-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1999 DEC 28 P 1:02

Barbara Toney Dierker
REGISTER OF DEEDS
BAY COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, Jerry L. Jones, in a field survey on June 18, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

- E-7 Corner common to Sections 16, 17, 20 and 21
- Survey by Glo, 1831, set post
Survey by Edmands Engineering, 1972, 1976, 1979, 1985, found nail
Survey by J. Schafer 1974, 1979, found 3/4" pipe
LCRC by E. Goss, 1972, found 1/2" bar
LCRC by E. Goss, 1972, found nail

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-7 Corner common to Sections 16, 17, 20 and 21
- Found 1/2" pipe per surveys by Edmands Engineering, J. Schafer, and LCRC by E. Goss

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-7 Corner common to Sections 16, 17, 20 and 21
- Replaced 1/2" pipe with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838 in mon box; and is accepted as the best available evidence of the position of the accepted corner
- S 42 Deg E, 50.08', centerline top of fire hydrant
S 45 Deg E, 47.98', west rod on top project marker (rec. 47.55' to face)
S 45 Deg W, 64.55', nail and disc #43066 W power pole
N 55 Deg W, 37.62', chiseled "+" in N end concrete pipe (rec)

Signed by Jerry L. Jones
Surveyor's Michigan License No. 19835

Date 12/09/99
Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
Revised May 14, 1971
Revised Jan., 1983

APPROVED LAND CORNER
P.A. 345 OF 1990 - Bay County
Date 7.30.99
MH
Michael MacDonald P.S.
County Representative



004 307