

1999

SECTION

REMON. COR. E-9, WILLIAMS TWP.
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Bay _____

(County)	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>3E</u>	<u>E-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN

1998 DEC - 7 A 8:38

RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, JERRY JONES, in a field survey on July 13, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-9 Corner common to Sections 20, 21, 28 and 29

- Survey by Gio, Harvey Parke, 1831, set post
- Survey by Hunter Whittier 1968, found 3/4" iron pipe
- Survey by Ayres Associates 1985, found 3/4" rod in monument box
- Survey by Wade-Trim 1996, found monument box

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9 Corner common to Sections 20, 21, 28 and 29

Found 1" rod in monument box per surveys by Hunter-Whittier, Ayres Associates and Wade-Trim.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9 Corner common to Sections 20, 21, 28 and 29

Found 1" rod in monument box per surveys by Hunter-Whittier, Ayres Associates and Wade-Trim. Replaced rod with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838 and is accepted as the best available evidence of the position of the accepted corner.

- North 45.70', south edge 8" steel joint
- S 30 Deg E, 53.48', nail in top guard rail post
- S 30 Deg W, 53.60', nail in top guard rail post
- N 45 Deg E, 19.30', southeast corner C.B. (back of curb)

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 24 Sept 98
MJM
 Michael MacDonald P.S.
 County Representative

Signed by Jerry L. Jones Date 12/01/98

Surveyor's Michigan License No. 19838