

MAR 27 1999

SECTION

REMON. COR. E-10, WILLIAMS TWP.  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Bay \_\_\_\_\_  
(County)

	Located in:	Corner Code #
1. Public Land Survey	T 14N R 3E	E-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS  
 BAY COUNTY, MICHIGAN

1998 DEC -7 A 8:39

RECORDED

Register of Deeds Stamp & File Number

I, JERRY JONES, in a field survey on August 12, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-10 1/4 Corner common to Sections 28 and 29  
  
 Survey by Glo, Harvey Parke, 1831, set post  
 Survey by Hunter Whittier 1968, found  
 Survey by Ayres Associates 1985, set 3/4" pipe



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-10 1/4 Corner common to Sections 28 and 29  
  
 Set rod and brass cap in monument box from witnesses per survey by Ayres Associates.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10 1/4 Corner common to Sections 28 and 29  
  
 Set rod and brass cap stamped Bay County Remonumentation PS 19838 in monument box from witnesses per survey by Ayres Associates and is the best available evidence of the position of the accepted corner.  
  
 N 40 Deg W, 98.18', chiseled "X" in southwest corner of southeasterly wingwall. Rec.  
 S 30 Deg W, 65.45', nail and tag in 8" cottonwood. Rec.  
 East 33.00', concrete monument. Rec.  
 S 20 Deg W, 117.30', nail and disc in 12" poplar  
 East 4.2', center line Carter Road. Rec.

APPROVED LAND CORNER  
 P.A. 345 OF 1990 - Bay County  
 Date 24 Sept 98  
MTM  
 Michael MacDonald P.S.  
 County Representative

Signed by Jerry L. Jones Date 12/01/98

Surveyor's Michigan License No. 19838

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971  
 Revised May 14, 1971  
 Revised Jan., 1983