

MAR 17 1999

SECTION

REMON. COR. E-11, WILLIAMS TWP. LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Bay (County)

Located in: Corner Code #

Table with 3 columns: Section description, Located in (T, R, S), and Corner Code # (E-11).

4. Lot No. , Recorded Plat
5. Private Claims

REGISTERED stamp with date 1998 DEC -1 A 8:37 and signature of Michael MacDonald.

I, JERRY JONES, in a field survey on July 17, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-11 Corner common to Sections 28, 29, 32 and 33
Survey by Gio, 1830's, set post, Harvey Parke, 1831
Survey by MDOT 1959, found corner
Survey by Edmands Engineering 1972, found mon box
Survey by Ayres Associates 1985, 1988, found 1/2" rod in mon box
LCRC by E. Goss 1973, mon box



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-11 Corner common to Sections 28, 29, 32 and 33
Found 1/2" rod in mon box, (dug 3' deep, found 1/2" rod 1 1/2' deep) per surveys by MDOT, Edmands Engineering, Ayres Associates and LCRC by E. Goss.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11 Corner common to Sections 28, 29, 32 and 33
Found 1/2" rod in mon box, per surveys by MDOT, Edmands Engineering, Ayres Associates and LCRC by E. Goss; replaced rod with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838 and is accepted as the best available evidence of the position of the accepted corner.
N 45 Deg W, 70.04', southwest corner Dow Corning sign
S 40 Deg W, 50.32', large nail in power pole (R as 50.50')
S 40 Deg E, 45.28', nail and BC disc in power pole (R as 45.4')
S 30 Deg E, 70.43', nail and BC disc in 42" Maple (R as 69.5')

APPROVED LAND CORNER
PA. 345 OF 1990 - Bay County
Date 6 Aug 98
MJM
Michael MacDonald P.S.
County Representative

Signed by [Signature] Date 8/26/98
Surveyor's Michigan License No. 19838