

RECORDED

REMON CORNER F-5, WILLIAMS TWP.  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in  
Bay \_\_\_\_\_  
(County)

Located in:	Corner Code #
T 14N R 3E	F-5
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

1999 DEC 28 P 1:02

*Barbara Torres Dowd*  
REGISTER OF DEEDS  
BAY COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Jerry L. Jones, in a field survey on June 18, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-5 1/4 Corner common to Sections 9 and 16  
Survey by Glo, 1831, set post  
Survey by J. Schafer, 1974, 1975, found  
Survey by Edmands Engineering, 1979, found 5/8" iron  
Survey by D. Burgin, 1993, found



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-5 1/4 Corner common to Sections 9 and 16

Found 1/2" rod on top of 1/2" rod at position indicated in surveys by J. Schafer, Edmands Engineering and D. Burgin.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-5 1/4 Corner common to Sections 9 and 16

Replaced 1/2" rod with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838 and set mon box; and is accepted the best available evidence of the position of the accepted corner

- S 75 Deg W, 211.82', nail in power pole
- N 85 Deg E, 229.16', W'ly bolt on North end box culvert
- S 85 Deg E, 216.66', chiseled "+" on South end box culvert
- S 68 Deg E, 133.01', pk nail in power pole (Rec. as 132.95')

Signed by Jerry L. Jones  
Surveyor's Michigan License No. 19838

Date 12/22/99

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971  
Revised May 14, 1971  
Revised Jan., 1983

004 310

APPROVED LAND CORNER  
P.A. 345 OF 1990 - Bay County  
Date 10/26/99  
MM  
Michael MacDonald P.S.  
County Representative