

REMON. COR. F-9
MAR 1 1899

SECTION

REMON. COR. F-9, WILLIAMS TWP.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Bay _____
(County)

1. Public Land Survey	T <u>14N</u> R <u>3E</u>	Corner Code # <u>F-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN
 1998 DEC - 1 A 8:37
 Register of Deeds Stamp & File Number
 RECORDED

I, JERRY JONES, in a field survey on July 13, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-9 1/4 Corner common to Sections 21 and 28
 Survey by Harvey Parke, 1831, set post
 Survey by Hunter-Whittier 1968, found remains wood stake, set 1/4" rod
 Survey by Ayres Associates 1985, found 1/2" rod and cap



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-9 1/4 Corner common to Sections 21 and 28
 Found 1/2" rod and Ayres cap by wood stake per surveys by Hunter-Whittier and Ayres Associates.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9 1/4 Corner common to Sections 21 and 28
 Found 1/2" rod and Ayres cap by wood stake per surveys by Hunter-Whittier and Ayres Associates. Replaced 1/2" rod with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838 and monument box; and is accepted as the best available evidence of the position of the original corner.
 South 21.37', northwest corner 8" x 8" concrete post. Rec 21.9 centerline
 North 31.48', nail and disc in 12" pine
 N 45 Deg E, 45.68', pk nail in fence post
 N 45 Deg W, 50.68', pk nail in fence post

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 12 Oct 98
MJM
 Michael MacDonald P.S.
 County Representative

Signed by Jerry L. Jones Date 12/01/98
 Surveyor's Michigan License No. 19838