

**REMON CORNER G-4, WILLIAMS TWP.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

For corners in SECTION _____
Bay _____
(County)

1999 DEC 28 P 1:02

Charles Thomas Oldham
REGISTER OF DEEDS
BAY COUNTY, MICHIGAN

	Located in:	Corner Code #
1. Public Land Survey	T 14N R 3E	G-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Jerry L. Jones, in a field survey on June 17, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2		1		
3													
4		7	8		9		10		11		12		
5													
6		18	17		16		15		14		13		
7													
8		19	20		21		22		23		24		
9													
10		30	29		28		27		26		25		
11													
12		31	32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-4 1/4 Corner common to Sections 9 and 10

Survey by Glo, 1831, set post
Survey by Edmands Engineering, 1972, 1974, found concrete nail, found iron
Survey by D. Burgin, 1984, 1990, 1991, found 3/8" rod
Survey by Wade-Trim, 1990, found 3/8" rod
Survey by D. Ledy, 1990, found
Survey by R.C. Engineering, 1995, found
Survey by J. Juras, 1996, found 3/8" rod
LCRC by L. McGinnis, 1974, nail



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4 1/4 Corner common to Sections 9 and 10

Found 3/8" rod per surveys by Edmands Engineering, D. Burgin, Wade-Trim, D. Ledy, J. Juras and fits witness on L. McGinnis LCRC.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4 1/4 Corner common to Sections 9 and 10

Replaced rod with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838; and is accepted as the best available evidence of the position of the accepted corner

N 88 Deg E, 38.50', pk nail in power pole (rec. as 38.45' and 38.61')
S 88 Deg E, 52.10', nail & disc in power pole (rec. as 52.15')
N 60 Deg W, 117.35', SE corner house (foundation)
N 20 Deg W, 125.48', SE corner concrete drive

Signed by Jerry L. Jones
Surveyor's Michigan License No. 19838

Date 12/10/99
Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
Revised May 14, 1971
Revised Jan., 1983

004 313

APPROVED LAND CORNER
P.A. 345 OF 1990 - Bay County
Date 10-21-99
MM
Michael MacDonald P.S.
County Representative