

**REMON. COR. G-5, WILLIAMS TWP.  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**RECORDED**

SECTION \_\_\_\_\_

For corners in

Bay \_\_\_\_\_  
(County)

Located in: Corner Code #

1. Public Land Survey

T 14N R 3E G-5

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1999 DEC 28 P 1:02

*Barbara Torres Oldham*  
REGISTER OF DEEDS  
BAY COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, **JERRY L. JONES**, in a field survey on June 16, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |   |    |    |    |    |    |    |   |   |   |   |   |   |
|----|---|----|----|----|----|----|----|---|---|---|---|---|---|
|    | A | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
| 2  |   | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |   |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  |   | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |   |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  |   | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |   |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  |   | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |   |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 |   | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |   |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 |   | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |   |    |    |    |    |    |    |   |   |   |   |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

G-5 Corner common to Sections 9, 10, 15 and 16

- Survey by Glo, 1831, set post
- Survey by Edmands Engineering, 1969, 1972, 1973, 1979, 1983, 1985, found 1/2" pipe
- Survey by J. Schafer, 1974, 1975, 1976, found 1/2" pipe
- Survey by D. Burgin, 1984, found 3/4" pipe; 1987, 1991, found 1/2" pipe
- Survey by Wade-Trim, 1989, 1994, 1995, found 1/2" pipe
- Survey by J. Jones, 1998, found 1/2" pipe
- LCRC by L. McGinnis, 1974, found 1/2" pipe
- LCRC by J. Schafer, 1974, found 1/2" pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5 Corner common to Sections 9, 10, 15 and 16

Found 1/2" pipe per surveys by Edmands Engineering, J. Schafer, D. Burgin, Wade-Trim, J. Jones and LCRC's by J. Schafer and L. McGinnis

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5 Corner common to Sections 9, 10, 15 and 16

Found 1/2" pipe, replaced pipe with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838 in monument box and accepted as the best available evidence of the position of the accepted corner.

- S 50 Deg W, 48.78', pk nail in power pole (Rec. as 49.4')
- N 65 Deg W, 80.15', nail in power pole (Rec. as 80.15')
- S 45 Deg E, 53.95', pk nail in power pole (Rec. as 54.03')
- S 45 Deg E, 54.05', nail & disc in power pole (Rec. as 53.98')
- N 60 Deg E, 47.17', pk nail in power pole (Rec. as 47.40')
- N 65 Deg W, 80.20', nail and survey disc in power pole (Rec. as 80.20')

Signed by *Jerry L. Jones*  
Surveyor's Michigan License No. 19838

Date 12/09/99  
Form approved by Michigan State Board of Land Surveyors, Jan. 20, 1971  
Revised May 14, 1971  
Revised Jan., 1983



APPROVED LAND CORNER  
P.A. 345 OF 1990 - Bay County  
Date 9.09.99  
MH  
Michael MacDonald P.S.  
County Representative

004 314