

REMON. COR. G-6, WILLIAMS TWP.  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in  
 Bay \_\_\_\_\_ SECTION \_\_\_\_\_  
 (County)

Located in: Corner Code #  
 T 14N R 3E G-6  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

1999 DEC 28 P 1:02

*Barbara Tolson DeWitt*  
 REGISTER OF DEEDS  
 BAY COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, JERRY L. JONES, in a field survey on June 8, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2		1		
3													
4		7	8		9		10		11		12		
5													
6		18	17		16		15		14		13		
7													
8		19	20		21		22		23		24		
9													
10		30	29		28		27		26		25		
11													
12		31	32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G-6 1/4 Corner common to Sections 15 and 16
- Survey by Glo, 1831, set post
  - Survey by Edmands Engineering, 1969, 1972, 1973, 1979, 1983, found pipe in mon box
  - Survey by J. Schafer, 1974, 1980, found pipe in mon box
  - Survey by D. Burgin, 1987, 1988, 1991, found 1/2" pipe
  - Survey by D. Ledy, 1987, found 3/4" pipe in mon box
  - Survey by J. Jones, 1990, 1998, found 1/2" rod
  - Survey by Wade-Trim, 1995, found 1/2" re-rod
  - LCRC by E. Goss, 1972, found 3/4" pipe in mon box
  - LCRC by D. Ledy, 1988, found 3/4" pipe in mon box



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-6 1/4 Corner common to Sections 15 and 16
- Found 5/8" rod at position indicated in surveys by Edmands Engineering, J. Schafer, D. Burgin, D. Ledy, J. Jones and Wade-Trim and LCRC's by E. Goss and D. Ledy

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-6 1/4 Corner common to Sections 15 and 16
- Found 5/8" re-rod, replaced re-rod with 5/8" re-rod and brass cap stamped Bay County Remonumentation PS 19838 in mon box and is accepted as the best available evidence of the position of the accepted corner.
- N 15 Deg W, 38.46', chiseled "+" in concrete headwall
  - N 15 Deg E, 135.40', centerline top fire hydrant (Rec. as 135.1')
  - East, 32.87', 2" pipe (Rec. as 32.87')
  - N 80 Deg W, 31.70', pk nail in power pole (Rec. as 31.70')
  - 2.5' West of centerline Eleven Mile Road

Signed by Jerry L. Jones  
 Surveyor's Michigan License No. 19838

Date 12/22/99

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971  
 Revised May 14, 1971  
 Revised Jan., 1983

004 315

APPROVED LAND CORNER  
 P.A. 345 OF 1990 - Bay County  
 Date 2.02.99  
MM  
 Michael MacDonald P.S.  
 County Representative