

MAR 7 1999

SECTION

REMON. COR. G-9, WILLIAMS TWP. LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Bay (County)

- 1. Public Land Survey Located in: T 14N R 3E Corner Code # G-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

1998 DEC -7 A 8:39 REGISTER OF DEEDS BAY COUNTY, MICHIGAN RECORDED

Register of Deeds Stamp & File Number

I, JERRY L. JONES, in a field survey on August 13, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Cell (9, G) contains a dot.

A. Description of original monument and accessories and/or subsequent restoration:

- G-9 Corner common to Sections 21, 22, 27 and 28
Survey by Glo, Harvey Parke, 1831, set post
Survey by MDOT, 1957, found
Survey by Hunter and Whittier, 1975, found
Survey by Ayres Associates, 1981, 1993, found 3/4" rod
Survey by Edmands Engineering, 1982, 1984, found mon box
Survey by Burgin, 1989, 1991, found 5/8" iron



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-9 Corner common to Sections 21, 22, 27 and 28
Found 3/4" rod in mon box per surveys by MDOT, Hunter-Whittier, Ayres Associates, Edmands Engineering, and Burgin

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-9 Corner common to Sections 21, 22, 27 and 28
Found 3/4" rod in mon box per surveys by MDOT, Hunter and Whittier, Ayres Associates, Edmands Engineering, and Burgin; replaced rod with 5/8" rod with brass cap stamped Bay County Remonumentation PS 19838, and is accepted as the best available evidence of the position of the accepted corner.
North, 35.40', south edge B" steel expansion joint, rec 35.3', 35.4', 35.18'
N 35 Deg W, 30.18', nail in top of guard rail post, rec 30.16'
N 35 Deg E, 30.20', nail in top of guardrail post, rec 30.17'
S 35 Deg W, 31.50', nail in top of guardrail post, rec 31.53'
APPROVED LAND CORNER
P.A. 345 OF 1990 - Bay County
Date 04 Sept 98
MJM
Michael MacDonald P.S.
County Representative

Signed by Jerry L. Jones Date 12/01/98
Surveyor's Michigan License No. 19838