

SECTION

REMON. COR. H-5, WILLIAMS TWP.  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in  
Bay \_\_\_\_\_  
(County)

Located in: Corner Code #

- 1. Public Land Survey  
T 14N R 3E      H-5  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling  
in Section      S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous  
Property in Sec.      S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

1999 DEC 28 P 1:02

*Barbara Torres Van Pelt*  
REGISTER OF DEEDS  
BAY COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, JERRY L. JONES, in a field survey on June 6, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-5    ¼ Corner common to Sections 10 and 15  
Survey by Glo, 1830's, set post  
Survey by J. Juras, 1996, railroad spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5    ¼ Corner common to Sections 10 and 15  
Found railroad spike with chiseled "+" per survey by J. Juras.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5    ¼ Corner common to Sections 10 and 15  
Found railroad spike, replaced with 5/8" rod with brass cap stamped Bay County Remonumentation PS 19838 in monument box and is accepted as the best available evidence of the position of the accepted corner.  
S 50 Deg E, 48.47', nail and B.C. Disc in power pole (48.73' Rec.)  
S 45 Deg W, 35.02', notch in South end 12' CMP  
S 85 Deg W, 237.19', nail and B.C. Disc in power pole  
South 5.2 ft. to centerline of road

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													



Signed by Jerry L. Jones  
Surveyor's Michigan License No. 19838

Date 12/29/99

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971  
Revised May 14, 1971  
Revised Jan., 1983

004 317

APPROVED LAND CORNER  
P.A. 345 OF 1990 - Bay County  
Date 9.09.99  
MM  
Michael MacDonald P.S.  
County Representative