

SECTION

REMON. COR. H-9, WILLIAMS TWP.  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Bay \_\_\_\_\_

(County)

Located in:

Corner Code #

1. Public Land Survey

T 14N R 3E

H-9

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_

R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_

R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_

R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_

R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

REGISTER OF DEEDS  
 BAY COUNTY, MICHIGAN

1998 DEC - 7 A 8 37

RECORDED

Register of Deeds Stamp & File Number

A B C D E F G H I J K L M

2	6	5	4	3	2	1
3						
4	7	8	9	10	11	12
5						
6	18	17	16	15	14	13
7						
8	19	20	21	22	23	24
9						
10	30	29	28	27	26	25
11						
12	31	32	33	34	35	36
13						

I, JERRY L. JONES, in a field survey on August 11, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

H-9 1/4 corner common to Sections 22 and 27

Survey by Harvey Parke, 1831, set post  
Survey by Hunter and Whittier, 1975, found

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-9 1/4 corner common to Sections 22 and 27

Found 2" pipe at location per survey by Hunter-Whittier.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9 1/4 corner common to Sections 22 and 27

Found 2" pipe per survey Hunter and Whittier, replaced pipe with 5/8" rod with brass cap stamped Bay County Remonumentation PS 19838, and is accepted as the best available evidence of the position of the accepted corner.

N 40 Deg W, 11.83', nail in 8" Oak  
S 89 Deg W, 8.53', nail in 6" Oak  
S 30 Deg W, 12.41', nail in 8" Oak  
North, 39.0', US 10 highway R/W fence  
Corner is 3 ft. West of edge of tilled field in brushline

APPROVED LAND CORNER  
P.A. 345 OF 1990 - Bay County  
Date 12 Nov 98  
MTM  
Michael MacDonald P.S.  
County Representative

Signed by Jerry L. Jones

Date 12/01/98

Surveyor's Michigan License No. 19838