

APR 17 1999

REMON. COR. H-11 WILLIAMS TWP.  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in  
Bay \_\_\_\_\_

(County)	Located in:	Corner Code #
1. Public Land Survey	T <u>14</u> N R <u>3E</u>	<u>H-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS  
 BAY COUNTY, MICHIGAN  
 1998 DEC -7 A 8:38  
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JERRY JONES, in a field survey on July 14, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

H-11 1/4 corner common to Sections 27 and 34  
  
 Survey by Glo, Harvey Parke, 1831, set post  
 Survey by Edmands Engineering 1983, 1987, 1988  
 Hunter-Whittier records in 1975



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11 1/4 corner common to Sections 27 and 34  
  
 Found 3/8" rod at location per surveys by Edmands Engineering and Hunter-Whittier records

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11 1/4 corner common to Sections 27 and 34  
  
 Found 3/8" rod per surveys by Edmands Engineering, removed rod, dug 3', found 3/8" rod 2' deep, replaced rods with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838 in mon box; and is accepted as the best available evidence of the position of the accepted corner.  
  
 S 45 Deg W, 42.69', pk nail in power pole, Rec. 42.2  
 N 40 Deg W, 42.38', pk nail in power pole, Rec. 42.1  
 S 35 Deg W, 71.9', centerline 6" Spruce  
 N 80 Deg E, 222.30', nail and BC disc in power pole  
 South 1', centerline Salzburg Road  
 East 7', center Saunders Road

APPROVED LAND CORNER  
 P.A. 345 OF 1990 - Bay County  
 Date 24 Sept 98  
MJM  
 Michael MacDonald P.S.  
 County Representative

Signed by Jerry L. Jones Date 12/04/98  
 Surveyor's Michigan License No. 19838