

REMON. COR. I-3, WILLIAMS TWP.
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in SECTION
 Bay _____
 (County)

	Located in:	Corner Code #
1. Public Land Survey	T 14N R 3E	1-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1999 DEC 28 P 1:02

Barbara Tonto DuPres
 REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, JERRY L. JONES, in a field survey on May 17, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-3 Corner common to Sections 2, 3, 10 and 11

- Survey by Glo, 1831, set post
- Survey by Edmands Engineering, 1965, 1971, found iron in monument box
- Survey by Hunter & Whittier, 1973, 1974, 1977, 1978, found 3/4" rod in monument box
- Survey by D. Burgin, 1991, found 3/4" pipe in water box
- Survey by Wade-Trim, 1991, 1995, found 3/4" iron in monument box
- Survey by J. Juras, 1996, found monument box
- Survey by D. Ledy, 1997, found 3/4" pipe in monument box
- LCRC by G. Delameter, 1971, found monument box
- LCRC by D. Richardson, 1997, 3/4" pipe in monument box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-3 Corner common to Sections 2, 3, 10 and 11

Found 3/4" pipe in monument box per surveys by Edmands Engineering, Hunter-Whittier, D. Burgin, Wade-Trim, J. Juras, D. Ledy and LCRC's by G. Delameter and D. Richardson

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-3 Corner common to Sections 2, 3, 10 and 11

Found 3/4" pipe, replaced pipe with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838 and is accepted as the best available evidence of the position of the accepted corner.

- S 45 Deg W, 51.71', nail and disc in power pole (Rec.)
- N 65 Deg W, 72.83', pk nail in power pole
- S 50 Deg E, 46.00', nail & disc in power pole stub (Rec.)
- N 45 Deg E, 52.94', nail & disc in power pole (Rec.)
- On centerline Wheeler Road (E & W)
- 2.2' West of centerline Garfield Road (N & S)

Signed by *Jerry L. Jones*
 Surveyor's Michigan License No. 19838

Date 12/10/99
 Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
 Revised May 14, 1971
 Revised Jan., 1983



004 318

APPROVED LAND CORNER
 P.A. 346 OF 1990 - Bay County
 Date 12/05/99
 MM
 Michael MacDonald P.S.
 County Representative