

**REMON. COR. I-4, WILLIAMS TWP.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

1999 DEC 28 P 1:02

Barbara Toles De Haven
REGISTER OF DEEDS
BAY COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

SECTION

For corners in
Bay _____
(County)

- | | | |
|---------------------------------------|--------------------------|---------------|
| 1. Public Land Survey | Located in: | Corner Code # |
| | T <u>14N</u> R <u>3E</u> | <u>I-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

I, **JERRY L. JONES**, in a field survey on May 17, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

- I-4 1/4 corner common to Sections 10 and 11
- Survey by Glo, 1831, set post
 Survey by J. Schafer, 1972, 1973, 1977, 1978, 3/4" pipe in monument box
 Survey by D. Burgin, 1991, monument box
 Survey by Wade-Trim, 1995, found 3/4" pipe in monument box
 Survey by J. Juras, 1996, 3/4" iron in monument box
 LCRC by G. Delamater, 1971
 LCRC by D. Richardson, 1997, 3/4" pipe in monument box



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-4 1/4 corner common to Sections 10 and 11
- Found 3/4" pipe in monument box per surveys by J. Schafer, D. Burgin, Wade-Trim, J. Juras and LCRC's by G. Delamater and D. Richardson

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-4 1/4 corner common to Sections 10 and 11
- Found 3/4" pipe in monument box, replaced pipe with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838 and is accepted as the best available evidence of the position of the accepted corner.
- East, 34.58', pk nail in fence post (Rec. as 34.32' in 1991 survey)
 N 15 Deg W, 105.95', nail and tag in 20" Ash (Rec. as 106.02' in 1991 survey)
 N 89 Deg W, 51.03', nail and disc in power pole (Rec. as 50.85' in 1977 survey)
 N 30 Deg E, 62.18', nail and disc in power pole
 4.03' West of centerline Garfield Road

Signed by *Jerry L. Jones*
 Surveyor's Michigan License No. 19838

Date 12/10/99

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
 Revised May 14, 1971
 Revised Jan., 1983

004 319

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 6.05.99
MM
 Michael MacDonald P.S.
 County Representative