

DEC 17 1998

REMON. COR. I-7, WILLIAMS TWP.
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Bay

(County)	Located in:	Corner Code #
1. Public Land Survey	T 14N R 3E	I-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN

1998 DEC -1 A 8:38

RECORDED

Register of Deeds Stamp & File Number

I, **JERRY JONES**, in a field survey on July 14, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-7 Corner common to Sections 14, 15, 22 and 23

- Survey by Glo, 1830's ±, set post, Harvey Parke, 1831
- Survey by Dow Chemical Co., 1959, found
- Survey by Hunter and Whittier, 1964, 1971, 1974, found mon box
- Survey by Edmands Engineering, 1971, 1972, 1974, 1976, 1978, 1979, 1985, 1988, 1992, found mon box
- Survey by Williams & Works, 1983, found "T" iron in mon box
- Survey by D. Burgin, 1987, found "T" iron in mon box
- Survey by Wade-Trim, 1995, 1997, found mon box
- LCRC by E. Goss, 1972, found mon box



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-7 Corner common to Sections 14, 15, 22 and 23

Found "T" bar and cap in mon box per surveys by Williams & Works, D. Burgin, Wade-Trim, and LCRC by E. Goss. Also fits survey by Dow Chemical Co., Hunter and Whittier, Edmands Engineering.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7 Corner common to Sections 14, 15, 22 and 23

Found "T" bar and cap in mon box (dug, found nothing) per surveys by Dow Chemical Co., Hunter Whittier, Edmands Engineering, Williams & Works, D. Burgin, Wade-Trim, and LCRC by E. Goss, replaced "T" bar with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838, and is accepted as the best available evidence of the position of the accepted corner.

- S 45 Deg E, 43.17', nail and disc in power pole
- N 40 Deg E, 52.96', pk nail in power pole (R as 52.95')
- N 50 Deg W, 63.32', nail in power pole (R as 63.40')
- S 50 Deg W, 53.66', pk nail in power pole (R as 53.1')
- S 45 Deg W, 59.72', centerline top fire hydrant (R as 59.70')
- N 10 Deg W, 9', manhole

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 6 Aug 98
MJM
 Michael MacDonald P.S.
 County Representative

Signed by Jerry L. Jones Date 8/26/98
 Surveyor's Michigan License No. 19838