

REMON. COR. J-3, WILLIAMS TWP.
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1999 DEC 28 P 1:02

Barbara Torres De France
 REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN

SECTION _____
 For corners in
 Bay _____
 (County)

Located in: Corner Code #

- | | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 14N R 3E | J-3 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

I, JERRY L. JONES, in a field survey on May 17, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

- J-3 1/4 corner common to Sections 2 and 11
- Survey by Glo, 1831, set post
 Survey by Edmands Engineering, 1965, 1993, found 5/8" rod in monument box
 Survey by J. Schafer, 1973, monument box
 LCRC by D. Whittier, 1972, found 5/8" rod in monument box



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-3 1/4 corner common to Sections 2 and 11
- Found 5/8" rod in monument box per surveys by Edmands Engineering, J. Schafer and LCRC by D. Whittier

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-3 1/4 corner common to Sections 2 and 11
- Replaced rod with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838 and is accepted as the best available evidence of the position of the accepted corner.
- N 50 Deg E, 128.57', pk nail in power pole
 N 60 Deg W, 126.70', pk nail in power pole (Rec. as 126.70')
 S 70 Deg W, 168.39', nail & disc in power pole
 S 80 Deg E, 286.33', centerline top fire hydrant
 On centerline Wheeler Road

Signed by Jerry L. Jones
 Surveyor's Michigan License No. 19838

Date 12/10/99

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
 Revised May 14, 1971
 Revised Jan., 1983

004 322

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 8.05.99
MM
 Michael MacDonald P.S.
 County Representative