

REMON. COR. J-5, WILLIAMS TWP.
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

SECTION _____

For corners in
 Bay _____
 (County)

- | | | |
|---------------------------------------|-------------------------|---------------|
| 1. Public Land Survey | Located in: | Corner Code # |
| | T 14N R 3E | J-5 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

1999 DEC 28 P 1:03

Barbara Towles DeWitt
 REGISTER OF DEEDS,
 BAY COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, JERRY L. JONES, in a field survey on May 17, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

- J-5 1/4 corner common to Sections 11 and 14
- Survey by Glo, 1831, set post
 - Survey by M. MacDonald, 1978, found 1" bar
 - Survey by D. Burgin, 1986, found 3/4" pipe
 - Survey by J. Jones, 1992, found 1" square shaft
 - LCRC by D. Whittier, 1972, found 1" square shaft
 - LCRC by M. MacDonald, 1979, found 1" iron



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-5 1/4 corner common to Sections 11 and 14
- Found buggy axle per surveys by M. MacDonald, D. Burgin, J. Jones and LCRC's by D. Whittier and M. MacDonald

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-5 1/4 corner common to Sections 11 and 14
- Replaced buggy axle with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838 in monument box and is accepted as the best available evidence of the position of the accepted corner.
- North 47.92', pk nail in power pole (Rec. as 47.79' in 1972 LCRC)
 - N 20 Deg W, 107.33', SE corner garage (foundation) (Rec. as 107.24' in 1992 survey)
 - S 5 Deg W, 20.90', centerline gas line marker (Rec. as 21.35' in 1972 LCRC)
 - S 10 Deg E, 20.03', end 12" CMP
 - On centerline Wilder Road

Signed by Jerry L. Jones
 Surveyor's Michigan License No. 19838

Date 12/10/99
 Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
 Revised May 14, 1971
 Revised Jan., 1983

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 8.05.99
MH
 Michael MacDonald P.S.
 County Representative