

**SURVEY & REMONUMENTATION**

**APR 23 1998**

**REMON COR. J-9, WILLIAMS TWP  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corner in SECTION  
Bay \_\_\_\_\_  
(County)

Located in: Corner Code #  
T 14N R 3E J-9  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

**RECORDED**  
**NOV 10 7 30 AM '97**  
*Michael MacDonald*  
**REGISTER OF DEEDS**  
**BAY COUNTY, MICHIGAN**  
 Register of Deeds Stamp & File Number

I, JERRY L. JONES, in a field survey on July 15, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

J-9 1/4 corner common to Sections 23 and 26  
 Government survey, 1830's, set post  
 LCRC, L. McGinnis, 1" pipe, L-02, P-41, (1977)  
 LCRC, D. Burgin, 1 1/2" pipe (1992), L-003, P-11



**WITNESS NOTE:** Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

J-9 1/4 corner common to Sections 23 and 26  
 Found 1 1/4" pipe, stones around, per LCRC's by L. McGinnis and D. Burgin

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

J-9 1/4 corner common to Sections 23 and 26  
 Found 1 1/4" pipe per LCRC's by L. McGinnis and D. Burgin, replaced pipe with 5/8" rod and brass cap stamped, Bay County Remonumentation PS 19838 in mon box, and is accepted as the best available evidence of the position of the accepted corner.  
 N 20 Deg E, 56.08', nail and Bay Co. disc in fence post (R)  
 S 35 Deg W, 59.3', centerline well  
 S 65 Deg W, 81.63', nail and Bay Co. disc in power pole  
 N 45 Deg W, 34.35', nail and Bay County disc in 12" Elm  
 North 4' ±, centerline gravel road (R)

APPROVED LAND CORNER  
 P.A. 345 OF 1990 - Bay County  
 Date 27 June 97  
*MJM*  
 Michael MacDonald P.S.  
 County Representative

Signed by Jerry L. Jones Date 11/05/97

Surveyor's Michigan License No. 19838

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971

Revised May 14, 1971

Revised Jan., 1983