SURVEY &
REMONUMENTATION

APR 23 1998

REMON COR. K-6, WILLIAMS TWP

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION
Bay
(County)

		Located in:	Corner Code #
1. Public Land Survey		T 14N R 3E	K-6
		T ___ R ___	
		T ___ R ___	
		T ___ R ___	
2. Property Controlling in Section	S ___	T ___ R ___	
	S ___	T ___ R ___	
3. Miscellaneous Property in Sec.	S ___	T ___ R ___	
	S ___	T ___ R ___	

RECORDED
Nov 10 7 30 AM '97
REGISTER OF DEEDS
BAY COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____



I, JERRY L. JONES, *in a field survey on* July 21, *19* 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the *corner points mentioned in lines 3, 4 and 5 above* were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be *recorded on this certificate.*

A. Description of original monument and accessories and/or subsequent restoration:

K-6 Corner common to Sections 13 and 14

Government survey, set post, 1831
LCRC by M. MacDonald, 1979, railroad spike, L-002, P-498

STATE OF MICHIGAN
JERRY L. JONES
PROFESSIONAL SURVEYOR
No. 19838
LICENSED PROFESSIONAL SURVEYOR

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6 Corner common to Sections 13 and 14

Set 5/8" rod in monument box at midpoint on line between K-5 and K-7 per LCRC by M. MacDonald, L-002, P-498
No corner evidence found after digging

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 Corner common to Sections 13 and 14

Set 5/8" rod with brass cap stamped, Bay County Remonumentation PS 19838 in mon box, per LCRC by M. MacDonald and is accepted as the best available evidence of the position of the accepted corner.

East 33.97', nail and disc in power pole
N 45 Deg E, 137.7', NW corner of house (R)
N 15 Deg E, 124.20', nail and Bay County disc in telephone pole
West 32.05', steel fence post
East 5'±, center line bit road (R)
on field line to west

APPROVED LAND CORNER
P.A. 345 OF 1990 - Bay County
Date 27 June 97
MJM
Michael MacDonald P.S.
County Representative

Signed by Jerry L. Jones Date 10/22/97

Surveyor's Michigan License No. 19838

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
Revised May 14, 1971
Revised Jan., 1983