

SURVEY & REMONUMENTATION

APR 23 1998

SECTION

REMON COR. K-9, WILLIAMS TWP  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Bay \_\_\_\_\_  
(County)

- 1. Public Land Survey Located in: T 14N R 3E Corner Code # K-9
- 2. Property Controlling in Section Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_
- 3. Miscellaneous Property in Sec. Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Michigan State Board of  
REGISTER OF DEEDS  
BAY COUNTY, MICHIGAN

Nov 10 7 30 AM '97

RECORDED

Register of Deeds Stamp & File Number

I, JERRY L. JONES, in a field survey on July 15, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-9 Corner common to Sections 23, 24, 25 and 26  
Government survey, 1830's, set post  
Survey by Burgin Land Surveys, 1990, found iron in mon box, L-1226, P-45  
LCRC by J. McMahon, found hand hole, L-002, P-227  
LCRC by D. Burgin, found iron in mon box, L-003, P-11



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9 Corner common to Sections 23, 24, 25 and 26  
Found 3/4" rod in mon box per surveys by Burgin Land Surveys and LCRC by J. McMahon and D. Burgin

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 Corner common to Sections 23, 24, 25 and 26  
Found 3/4" rod in mon box per surveys by Burgin Land Surveys and LCRC by J. McMahon and D. Burgin, replaced rod with 5/8" rod and brass cap stamped, Bay County Remonumentation PS 19838, and is accepted as the best available evidence of the position of the accepted corner.  
NE, 29.70', SW corner C.B., (R) N 88 Deg W, 16.50', nail and BC disc in guardrail post  
North, 50.88', centerline bridge expansion joint (R) N 88 Deg E, 16.67', nail and BC disc in guardrail post  
NE, 46.15', SW corner east bridge abutment (R)  
NW, 46.24', SE corner West bridge abutment (R)  
N 88 Deg W, 19.60', nail and disc in guardrail post (R)  
N 88 Deg E, 19.61', nail and disc in guardrail post (R)

APPROVED LAND CORNER  
P.A. 345 OF 1990 - Bay County  
Date 27 June 97  
HJM  
Michael MacDonald P.S.  
County Representative

Signed by Jerry L. Jones Date 10/22/97

Surveyor's Michigan License No. 19838