

# SURVEY & REMONUMENTATION

APR 23 1998

## REMON. COR. K-10, WILLIAMS TWP. LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION  
Bay  
(County)

	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>3E</u>	<u>K-10</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS  
 BAY COUNTY, MICHIGAN  
 Nov 10 7 30 AM '97  
 RECORDED

Register of Deeds Stamp & File Number

I, JERRY JONES, in a field survey on July 18, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

K-10 1/4 corner common to Sections 25 and 26  
  
Government survey, 1830's, set post  
Survey by Burgin Land Surveys, 1990, found railroad spike, L-1220, P-45



**WITNESS NOTE:** Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K-10 1/4 corner common to Sections 25 and 26  
  
Found railroad spike per survey by Burgin Land Surveys

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-10 1/4 corner common to Section 25 and 26  
  
Found railroad spike per survey by Burgin Land Surveys, replaced railroad spike with 5/8" rod and brass cap stamped Bay County Remonumentation, PS 19838, in mon box and is accepted as the best available evidence of the position of the accepted corner.  
  
N 85 Deg W, 39.61', nail and Bay Co. disk in power pole  
S 60 Deg W, 37.05', centerline gas marker post C37  
S 75 Deg E, 32.18', centerline top fire hydrant (R)  
N 80 Deg E, 35.37', nail and tag in power pole  
N 60 Deg E, 107.19', NW corner of house (R)

APPROVED LAND CORNER  
P.A. 345 OF 1990 - Bay County  
Date 22 June 97  
MTM  
Michael MacDonald P.S.  
County Representative

Signed by Jerry L. Jones Date 10/22/97