

SURVEY & REMONUMENTATION

APR 23 1998

REMON. COR. K-11, WILLIAMS TWP.
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
 For corners in
 Bay _____
 (County)

1. Public Land Survey	T <u>14</u> N R <u>3E</u>	Corner Code # <u>K-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTERED
 Nov 10 7 39 AM '97
 Register of Deeds Stamp & File Number
 REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN


I, JERRY JONES, in a field survey on July 18, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- K-11 Corner common to Sections 25, 26, 35 and 36
 - Government survey, 1831, set post, H. Paske
 - Survey by M. Hunter, 1962, found, unrecorded
 - Survey by Hunter-Whittier, 1978, Found 3/4" shaft in mon box, L-836, P-873
 - Survey by Burgin Land Surveys, 1988, 1989, found pk nail, L01096, P-405 and L-1135, P-212
 - Survey by Wade-Trim, 1992, found 1" bar, L-1242, P-609
 - LCRC by J. Schafer, 1973, Found 1" iron in mon box, L-002, P-27



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-11 Corner common to Sections 25, 26, 35 and 36
 - Found 1" shaft in mon box per survey by Hunter, Hunter-Whittier, Burgin Land Surveys, Wade-Trim, and LCRC by J. Schafer

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-11 Corner common to Section 25, 26, 35 and 36
 - Found 1" shaft per surveys by Hunter, Hunter-Whittier, Burgin Land Surveys, Wade-Trim, and LCRC by J. Schafer, replaced shaft with 5/8" rod and brass cap stamped Bay County Remonumentation, PS 19838, in mon box and is accepted as the best available evidence of the position of the accepted corner.
 - N 60 Deg W, 75.00', centerline hydrant (R)
 - S 40 Deg W, 43.32', nail & tag in telephone pole (R)
 - N 45 Deg E, 66.35", pk nail in telephone pole (R)
 - N 55 Deg W, 58.34', nail and disc in power pole
 - S 50 Deg E, 42.42', chiseled "+" in headwall

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 27 June 97
MJM
 Michael MacDonald P.S.
 County Representative

Signed by Jerry L. Jones Date 10/22/97

Surveyor's Michigan License No. 19838