

**SURVEY & REMONUMENTATION**

APR 23 1998

REMON. COR. K-13, WILLIAMS TWP.  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in  
 Bay \_\_\_\_\_  
 (County)

- |                                       |                   |       |
|---------------------------------------|-------------------|-------|
| 1. Public Land Survey                 | T 14N R 3E        | K-13  |
|                                       | T ___ R ___       | _____ |
|                                       | T ___ R ___       | _____ |
|                                       | T ___ R ___       | _____ |
| 2. Property Controlling in Section    | S ___ T ___ R ___ | _____ |
|                                       | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec.     | S ___ T ___ R ___ | _____ |
|                                       | S ___ T ___ R ___ | _____ |
| 4. Lot No. _____, Recorded Plat _____ |                   |       |
| 5. Private Claims _____               |                   |       |

REGISTER OF DEEDS  
 BAY COUNTY, MICHIGAN  
 Nov 10 7 30 AM '97  
 RECORDED

Register of Deeds Stamp & File Number

I, JERRY JONES, in a field survey on July 18, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- K-13 Corner common to Sections 35 and 36 on south townline
- Government survey, 1830's, set post  
 Survey by Edmands Engineering, 1977, found iron, L-827, P-91  
 LCRC by I. McGinnis, 1972, found rerod, L-001, P-115  
 LCRC by J. Schafer, 1973, Found 3/8" rerod, set pipe, L-002, P-29



**WITNESS NOTE:** Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- K-13 Corner common to Sections 35 and 36 on south townline
- Found 5/8" rod per survey by Edmands Engineer and LCRC's by L. McGinnis and J. Schafer

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- K-13 Corner common to Section 35 and 36 on south townline
- Found 5/8" rod per surveys by Edmands Engineering and LCRC's by fL. McGinnis and J. Schafer, replaced rod with 5/8" rod and brass cap stamped Bay County Remonumentation, PS 19838, in mon box and is accepted as the best available evidence of the position of the accepted corner.
- N 55 Deg E, 77.62', nail and disc in power pole (R)  
 N 60 Deg W, 51.43', notch in 24" CMP  
 S 70 Deg W, 52.12", chiseled "+" in 24" CMP  
 N 15 Deg W, 161.90', nail and Bay County disc in power pole

APPROVED LAND CORNER  
 P.A. 345 OF 1990 - Bay County  
 Date 27 June 97  
MJM  
 Michael MacDonald P.S.  
 County Representative

Signed by Jerry L. Jones Date 11/05/97

Surveyor's Michigan License No. 19838