

SURVEY & REMONUMENTATION

APR 23 1998

BAY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

BAY Located in: WILLIAMS TWP Corner Code #
(County)

1. Public Land Survey T 14N R 3E L-3
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN
 Dec 30 3 51 PM '97
 RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, BRIAN D FERGUSON, in a field survey on MAY 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-3 WOOD POST SET BY JOHN MULLETT IN 1830 - 31
NO EVIDENCE OF ORIGINAL CORNER REMAINS
NO LCRC'S RECORDED FOR THIS CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


L-3 FOUND 1/2" ROD
POSITION AGREES WITH SURVEYS RECORDED IN L 832 P 189; L 824 P 733'; L 1090 P 223

THIS POSITION IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3 SET 5/8" ROD W/3" BRASS BAY COUNTY REMONUMENTATION DISK IN MONUMENT BOX

SOUTH	11.75'	S. EDGE OF PAVEMENT
N02E	28.28'	TOP CTR OF 12" C.M.P.
N05E	63.87'	NAIL & TAG IN PWR POLE
N45E	50.15'	CTR OF 4" TESTWELL



Signed by Brian D Ferguson
Surveyor's Michigan License No. 26454

Date NOVEMBER 1997

APPROVED LAND CORNER
P.A. 345 OF 1990 - Bay County
Date 31 July 97
MTM
Michael MacDonald P.S.
County Representative