

SURVEY & REMONUMENTATION

APR 23 1998

REMON COR. M-8, WILLIAMS TWP
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
 For corners in
 Bay _____

(County)

Located in: Corner Code #

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>14N</u> R <u>3E</u> | <u>M-8</u> |
| | T <u>14N</u> R <u>4E</u> | <u>A-8</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN
 Nov 10 7 29 AM '97
 RECORDED

Register of Deeds Stamp & File Number

I, JERRY L. JONES, in a field survey on July 15, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-8/~~A-8~~ Corner common to Sections 24, T14N-R3E and 19, T14N-R4E

- Government survey, set post, 1830's
- Edmands Engineering, found mon box 1971, 1976, 1984, 1987, L-664, P-195 and L-799, P-268 and L-1177, P-22 and L-1062, P-460 and L-1402, P-185
- Wade-Trim, found "T" iron in mon box, 1991, 1996
- Burgin Land Surveys, found "T" iron in mon box, 1992, L-1307, P-932
- LCRC, L. McGinnis, found "T" iron in mon box, 1992, L-003, P-08



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8/~~A-8~~ Corner common to Sections 24, T14N-R3E and 19, T14N-R4E

Found "T" iron in mon box per surveys by Edmands Engineering, Wade-Trim, Burgin Land Surveys, and LCRC by L. McGinnis

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8/~~A-8~~ Corner common to Sections 24, T14N-R3E and 19, T14N-R4E

Found "T" iron in mon box, replaced iron with 5/8" rod and brass cap stamped, Bay County Remonumentation PS 19838, per survey by Edmands Engineering, Wade-Trim, Burgin Land Surveys, and LCRC by L. McGinnis in mon box and is accepted as the best available evidence of the position of the accepted corner.

- S 40 Deg E, 48.08', center line top hydrant (R)
- S 40 Deg W, 58.08', nail in power pole (R)
- N 45 Deg W, 62.52', nail in power pole (R)
- N 50 Deg E, 43.87', nail in power pole (R)

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 27 June 97
M.T.M.
 Michael MacDonald P.S.
 County Representative

Signed by Jerry L. Jones Date 10/22/97

Surveyor's Michigan License No. 19838