

SURVEY & REMONUMENTATION

APR 23 1998

REMON COR. M-6, WILLIAMS TWP
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION _____
 Bay _____
 (County)

Located in: Corner Code #
 T 14N R 3E M-6
 T 14N R 4E A-6
 T R
 T R
 S T R
 S T R
 S T R
 S T R

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECORDED
 Nov 10 7 29 AM '97
 REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN
 Register of Deeds Stamp & File Number

I, JERRY L. JONES, in a field survey on July 15, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6/A-6 Corner common to Sections 13, T14N-R3E and 18, T14N-R4E

Government survey, 1839, J. Mullett, set wood post
 Survey by L. McGinnis, 1972, Found 3/8" bent rod, L 691, P 597

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6/A-6 Corner common to Sections 13, T14N-R3E and 18, T14N-R4E

Found 3/8" rod 4' long, top bent in loop with stones around, per survey by L. McGinnis



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6/A-6 Corner common to Sections 13, T14N-R3E and 18, T14N-R4E

Found 3/8" rod, top bent in loop, replaced rod with 5/8" rod and brass cap stamped, Bay County Remonumentation PS 19838 in mon box, per survey by L. McGinnis and is accepted as the best available evidence of the position of the accepted corner.

N 50 Deg E, 226.10', SW corner of pole building
 N 15 Deg E, 198.85', nail and Bay County disc in power pole
 S 60 Deg W, 54.84', nail in power pole (R)
 N 5 Deg E, 374.96', center line top hydrant
 East 12', center line 8 Mile Road

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 27 June 97
 HJM
 Michael MacDonald P.S.
 County Representative

Signed by Jerry L. Jones

Date 10/22/97

Surveyor's Michigan License No. 19838

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971

Revised May 14, 1971

Revised Jan., 1983