

**SURVEY &
REMONUMENTATION**

APR 23 1998

SECTION

**REMON COR. M-7, WILLIAMS TWP
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Bay
(County)

Located in: Corner Code #

- | | | |
|---------------------------------------|----------------------------|------------|
| 1. Public Land Survey | T <u>14</u> N R <u>3</u> E | <u>M-7</u> |
| | T <u>14</u> N R <u>4</u> E | <u>A-7</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling
In Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous
Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Michael MacDonal
**REGISTER OF DEEDS
BAY COUNTY, MICHIGAN**

NOV 10 7 29 AM '97

RECORDED

Register of Deeds Stamp & File Number

I, JERRY L. JONES, in a field survey on July 15, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-7/A-7 Corner common to Sections 13 and 14, T14N-R3E & 18 and 19, T14N-R4E

- Government survey, 1839, set post, J. Mullett
- Survey by P. Ciosek, 1984, found iron, L-962, P-725
- Survey by D. Burgin, 1986, 1992, found 1/2" iron, L-1035, P-507 and L-1307, P-932
- Survey by L. McGinnis, 1987, found iron, L-1062, P-460

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7/A-7 Corner common to Sections 13 and 14, T14N-R3E & 18 and 19, T14N-R4E

Found 1/2" rod with stones around per surveys by P. Ciosek, D. Burgin and L. McGinnis



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7/A-7 Corner common to Sections 13 and 14, T14N-R3E & 18 and 19, T14N-R4E

Found 1/2" rod, replaced 1/2" rod with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838 in mon box, per surveys by P. Ciosek, D. Burgin and L. McGinnis and is accepted as the best available evidence of the position of the accepted corner.

- East, 44.62', center line top telephone box (R)
- N 45 Deg E, 103.2', SW corner house #4489 (R)
- N 25 Deg E, 114.70', center line top hydrant (R)
- S 80 Deg W, 37.25', nail and disc in power pole (R)
- East, 11' to centerline of 8 Mile Road

APPROVED LAND CORNER
P.A. 345 OF 1990 - Bay County
Date 27 June 97
MJM
Michael MacDonald P.S.
County Representative

Signed by Jerry L. Jones Date 10/22/97

Surveyor's Michigan License No. 19838