

SURVEY & REMONUMENTATION

APR 26 1995

BAY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**
Bay
 (County)

	Located In:	Corner Code #/
1. Public Land Survey	T 14 N, R 4 E.	K-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN

DEC 9 9 55 AM '94

RECORDED

003 134

Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
 2. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Ronald C. Prevost in a field survey on June 13, 1994, to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

- K-1 Post Set by John Mullett 1839
- W. Oak 18" N.55°W. 27 Lks.
- Birch 8" N.58°E. 24 Lks.
- LCRC, L.1, P.133, Iron, McGinnis 1972
- LCRC, L.2, P.597, 3/4" Pipe, Hughes 1989
- Recorded Survey - L.980, P.897

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-1 Found 1" Pipe about 40" Long & recorded witnesses
- SW 159.5 to E. Leg Tower (159.5 M)
- S 86.52 Nail in 8" Yellow Pine (86.50 M)
- S.20°W. 159.2 E Leg of Tower #1521 (159.5 M)

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-1 Placed 5/8" Rerod with 2 3/4" Bay Co. Brass Cap in 3" x 30" conc. filled pipe and Mon. Box. (Found pieces of glazed ceramic tile while digging to set Mon.)
- E Leg High-Tension Tower S.25°W. 159.50
- SW corner Pole Barn N.30°E. 81.48
- Nail & Ribbon E. Face 12" Pine S.01°E. 86.50
- Nail & Washer W. Face Light Pole S.20°W. 159.50

APPROVED LAND CORNER
 P.A. 345 OF 1990, - Bay County
 Date 6 Oct 94
M.M.
 Michael MacDonald P.S.
 County Representative

Signed by Ronald C. Prevost
 Surveyor's Michigan License No. 24612

