

SURVEY & REMONUMENTATION BAY COUNTY REMONUMENTATION

APR 26 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**
Bay
(County)

Located In: Corner Code //

- | | | |
|------------------------------------|-------------------------|-----|
| 1. Public Land Survey | T 14 N. R 4 E. | K-6 |
| | T _____ R _____ | |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

REGISTER OF DEEDS
 BAY COUNTY MICHIGAN
 Dec 9 9 56 AM '94

RECORDED

003 139
Register of Deeds Stamp & File Number

Ronald C. Prevost in a field survey on June 14, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

- K-6 Post Set by John Mullett 1839
 Beech 6" N.27°W. 9 Lks.
 Beech 12" S.54°W. 18 Lks.
 LCRC, L.1, P.381, Goss 1972
 LCRC, L.2, P.125, 3/8" Iron, McGinnis 1974
 LCRC, L.2, P.599, T Iron, Hughes 1989
 Recorded Surveys - L.874, P.740, L.745, P.510, L.798, P.605, L.812, P.242, L.866, P.952

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-6 Found P.K. Nail & recorded Witnesses as follows:
 98.2 to NW corner Foundation House (98.0 M)
 SW Nail in P Pole 39.83 (39.92 M)
 W 39.5 to P Pole (39.5 M)
 S.20°E. 102.21 to Fire Hydrant Valve Stem (102.33 M)
 W 39.82 P Pole P.K. N Face (39.92 M)
 S.10°E. 102.0 Top Hydrant (102.33 M)
 N.13°W. 94.20 8" Maple P.K. NE Face (94.00 M)
 NW 102.24 to SE corner House (102.24 M)

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 7 Aug 94
MM
 Michael MacDonald P.S.
 County Representative

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-6 Placed 5/8" Rerod & 2 3/4" Bay Co. Brass Cap & Mon. Box in place of P.K. Nail
 P.K. Nail in N Face P Pole S.89°W. 39.92
 Bay Co. Washer & Nail in W Face 12" Apple S.85°E. 36.68
 Center Hydrant S.20°E. 102.33
 P.K. Nail in E. Face 24" Maple N.20°W. 94.00
 SE Corner Block Foundation House N50°W. 102.24

Signed by Ronald C. Prevost
 Surveyor's Michigan License No. 24612

Date 11-30-94

