

SURVEY & REMONUMENTATION

APR 26 1995

COMMISSION

BAY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Bay

(County)

Located In:

Corner Code //

- 1. Public Land Survey T 14 N. R. 4 E. K-8
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Registration of Deeds
 BAY COUNTY MICHIGAN

Dec 9 9 56 AM '94

RECEIVED

003 141

Register of Deeds Stamp & File Number

- 1. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Ronald C. Prevost in a field survey on June 1, 19 94, to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

- K-8 Post Set by John Mullett 1839
- Beech 4" S.54°W. 23 Lks.
- Sugar 12" S.14°E. 20 Lks.
- LCRC, L.2, P.155-6, 1" Bar/Mon. Box, Leach 1975
- LCRC, L.2, P.347-8 Mon. Box, McGinnis 1977

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-8 Found Boat Spike in Mon. Box
- LCRC, L.2, P.155-6 N.45°E. 43.40 Nail & Tag #19001 W Side PP
- S.45°E. 49.10 Nail & Tag #19001 W Side PP
- S.45°W. 45.60 Nail & Tag #19001 E Side PP
- LCRC, L.2, P.347-8 NW 49.62 S Leg of Tower
- SE 60.0 Hydrant Valve Stem
- NE 43.65 Nail & Cap in P & T Pole

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 17 July 94
MM
 Michael MacDonald P.S.
 County Representative

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-8 Placed 5/8" Rod & 2 3/4" Bay Co. Brass Cap in existing Mon. Box in place of Boat Spike
- Nail & Cap NE Face P Pole N.45°W. 48.15
- Nail & Washer W Face P & T Pole N.45°E. 43.72
- Nail & Washer W Face P & T Pole S.45°E. 48.92
- Nail & Cap E Face P & T Pole S.45°W. 45.48

Signed by Ronald C. Prevost
 Surveyor's Michigan License No. 24612



11-30-94