

SURVEY & REMONUMENTATION

APR 26 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Bay

(County)

Located In:

Corner Code //

1. Public Land Survey	T	14 N	R	4 E.	L-5
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN

Dec 9 9 56 AM '94

RECORDED



003 143

Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
2. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Ronald C. Prevost in a field survey on June 11, 1994

to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

L-5 Post Set by John Mullett 1839
 Elm 7" S.29°E. 6 Lks.
 B. Ash 20" N.74°W. 24 Lks.
 LCRC - L.2, P.600 3/4" Iron in PVT Box, Hughes 1989
 LCRC - L.3, P.76 3/4" Iron Mon. Box, Juras 1994
 Recorded Surveys L.881, P.135, L.737, P.573, L.1014, P.411, L.1014, P.434, L.834, P.486, L.866, P.952

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5 Found 1" Bar in Mon. Box from LCRC & recorded survey witnesses
 N.15°W.25.10 Guard Post W/SPK 25.10 (25.18 M)
 S.10°W. 41.85 Guard Post W/SPK 41.85 (41.91 M)

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 23 June 94
 14 17
 Michael MacDonald P.S.
 County Representative

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5 Placed 5/8" Rebar with 2 3/4" Bay Co. Brass Cap over 1" Bar in existing Mon. Box
 Nail & Tag Top Guard Rail Post N.45°E. 28.65
 Nail & Tag Top Guard Rail Post N.10°W. 25.18
 Nail & Tag Top Guard Rail Post S.02°E. 41.91
 Nail & Tag Top Guard Rail Post S.50°E. 65.35

Signed by Ronald C. Prevost
 24612

Surveyor's Michigan License No. _____



11-30-94