

**SURVEY & REMONUMENTATION**

APR 26 1995

COMMISSION

**BAY COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**Bay**

(County)

Located In:

Corner Code: #

|                                    |   |               |               |            |
|------------------------------------|---|---------------|---------------|------------|
| 1. Public Land Survey              |   | <u>T 4 N.</u> | <u>R 4 E.</u> | <u>M-2</u> |
|                                    |   | T             | R             |            |
|                                    |   | T             | R             |            |
|                                    |   | T             | R             |            |
| 2. Property Controlling in Section | S | T             | R             |            |
|                                    | S | T             | R             |            |
| 3. Miscellaneous Property in Sec.  | S | T             | R             |            |
|                                    | S | T             | R             |            |

Michigan State Board of Land Surveyors  
 REGISTER OF DEEDS  
 BAY COUNTY, MICHIGAN

Dec 7 11 17 AM '94

RECORDED

**003 132**

Register of Deeds Stamp & File Number

1. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 2. Private Claims \_\_\_\_\_

Ronald C. Prevost in a field survey on June 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 2  | 6  | 5  | 4  | 3  | 2  |    |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

1. Description of original monument and accessories and/or subsequent restoration:

M-2 Post Set by John Mullett 1839  
 Aspen 7 S.53°W. 12 Lks.  
 Aspen 4 N.10°W 30 Lks.  
 LCRC L.1, P.539  
 LCRC L.2, P.601 - Hughes 1989  
 Recorded surveys L.695, P.83, L.907, P.299, L.687, P.319, L.866, P536, L.1035, P.512  
 Corner M-2 is common with A-2, T.14 N.-R.5 E.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2 Found 1/2" Bar per LCRC L.2, P.601  
 Found Rec'd witnesses as follows:  
 SE 57.15 (57.19 M) P. Pole w/nail N Face  
 N.25°E. 91.30 (91.00 M) P. Pole w/nail NW Face

APPROVED LAND CORNER  
 P.A. 345 OF 1990 - Bay County  
 Date 06/23/94  
H M  
 Michael MacDonald P.S.  
 County Representative

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 Placed Mon. Box, Bay Co. 2 3/4" Brass Cap on Existing Bar  
 Nail & M.D.O.T. Cap N. Face P & T Pole S.80°W. 42.48  
 Nail & M.D.O.T. Cap N. Face P & T Pole S.25°E. 57.19  
 Nail & M.D.O.T. Cap W. Face P & T Pole N.25°E. 91.00  
 Center Hydrant N.15°W. 124.94



Signed by Ronald C. Prevost  
 Surveyor's Michigan License No. 24612

Date 12-2-94