

# SURVEY & REMONUMENTATION

APR 26 1995

## BAY COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Bay

(County)

Located In:

Corner Code -##

- |                                    |                               |       |
|------------------------------------|-------------------------------|-------|
| 1. Public Land Survey              | T <u>14</u> N. R. <u>4</u> E. | M-8   |
|                                    | T _____ R _____               | _____ |
|                                    | T _____ R _____               | _____ |
|                                    | T _____ R _____               | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____       | _____ |
|                                    | S _____ T _____ R _____       | _____ |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____       | _____ |
|                                    | S _____ T _____ R _____       | _____ |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Ronald C. Prevost, in a field survey on June 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

1. Description of original monument and accessories and/or subsequent restoration:

- M-8 Post Set by John Mullett 1839  
Maple 24" N.86°W. 11 Lks.  
Beech 6" S.30°W. 41 Lks.  
LCRC, L.1, P.499-500 Mon. Box, Goss 1972  
SW 45.7 P.P., NE 48.44 F.H.  
Corner M-8 is common with A-8, T.14 N.-R.5 E.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-8 Found 3/8" Rod w/cap #25835 Ciosek, in Mon. Box.  
Distance M-8 to M-7 2637.77 compares with 2638.00 Wade-Trim

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-8 Placed 5/8" Rod & Bay Co. 2 3/4" Brass Cap in Place of 3/8" Rod in existing Mon Box.  
Center Hydrant N.65°E. 64.54  
Center M.H. N.65°W. 33.56  
Center M.H. S.01°E. 15.38  
Center W.M. Valve Box N.01°E. 31.02

APPROVED LAND CORNER  
P.A. 345 OF 1990 - Bay County  
Date 08/04/94  
MM  
Michael MacDonald P.S.  
County Representative

REGISTER OF DEEDS  
BAY COUNTY, MICHIGAN  
Dec 7 11 27 AM '94

RECORDED

**003 133**  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by Ronald C. Prevost  
Surveyor's Michigan License No. 24612

Date 12-2-94

